

Table 2 Summary of Bomboré Agglomeration Optimization Test Results

Cement added kg/t	Crush size (P100) mm	Flow rate L/m ² /hr	Pellet Quality
AM21 - Mixed material			
3	15	13,571	Good
*3	15	4,266	Fair
6	15	18,360	Very good
AM22 - Mixed material			
3	15	14,245	Good
*3	15	4,338	Fair
6	15	19,420	Very good
AM31 - Oxide material			
6	25	10,906	Poor/fair
7	25	16,153	Good
8	25	16,210	Good
*9	25	6,396	Excellent
AM32 - Oxide material			
6	25	4,938	Poor/fair
7	25	4,707	Poor
*8	25	13,307	Good/Fair
9	25	4,586	Excellent
*Results of 44-day column leach test			
Optimal cement dosage			